

पनवेल महानगरपालिका जाहीर निविदा दरपत्रक

आयुक्त, पनवेल महानगरपालिका हद्दीतील भुखंड क्र.८अ + ८ब, सेक्टर-१८, नवीन पनवेल (पश्चिम) या भुखंडावर माता व बालसंगोपन केंद्र उभारणे. या कामाचे अंदाजपत्रक बनविण्याकरीता दर मागविणे बाबत. या कामाचे अंदाजपत्रक बनविण्याकरीता खाली नमूद केलेल्या बाबींकरीता खालील नमूण्यात दर मागविण्यात येत आहे.

अ.क्र.	कामाचे नाव	मुदत
१	पनवेल महानगरपालिका हद्दीतील भुखंड क्र.८अ + ८ब, सेक्टर-१८, नवीन पनवेल (पश्चिम) या भुखंडावर माता व बालसंगोपन केंद्र उभारणे. या कामाचे अंदाजपत्रक बनविण्याकरीता दर मागविणे बाबत.	०२/०९/२०२६ ते ०८/०९/२०२६ (७ दिवस)

Specification

Sr. No	DESCRIPTION	Unit	Quantity	Rate
1.	Supply, Installation, Testing and commissioning of UL Certified / CPRI Tested Maintenance Free Earthing comprising of Electrode of 17.2 mm diameter Low Carbon Steel with 250 micron Molecular Copper Bonded Earthing Rod of Length 2.5m along with 25 kg Carbon Based environment friendly back fill Ground Enhancing compound required to fill up the excavated earth with required quantity as per specification no EA-MOBI (with 24 months warranty)	Each	78	
2.	Supply, Installation, Testing and commissioning of UL Certified / CPRI Tested Maintenance Free Earthing comprising of Electrode of 40 mm diameter Low Carbon Steel with 250 micron Molecular Copper Bonded Earthing Rod of Length 2.5m along with 25 kg Carbon Based environment friendly back fill Ground Enhancing compound required to fill up the excavated earth with required quantity as per specification no EA-MOBI (with 24 months warranty)	Each	14	
3.	Supply, installation, testing and commissioning of 25 x 6mm CU. Equipotential bar of 500 mm length with suitable junction box, base insulators and Cadmium plated bolt ,double nut ,plate & spring washer fastener sets for take-off connections. junction box to connect earthing conductor from building earthing to the equipment. (With six knock outs for connecting the equipment earthing with 10 set M12 fastener and base insulator (with 24 months warranty)	Each	24	
4.	Supply, installation, testing and commissioning of 50 x 6mm GI. Equipotential bar of 1000 mm length with suitable junction box, base insulators and Cadmium plated bolt ,double nut ,plate & spring washer fastener sets for take-off connections. junction box to connect earthing conductor from building earthing to the equipment. (With six knock outs for connecting the equipment earthing with 10 set M12 fastener and base insulator (with 24 months warranty)	Each	24	
5.	Designing, Supply, installation , Testing & Commissioning of below mentioned Lightning Protection System to complete the Job. 1. Vertical air terminal with accessories: 8 mm Aluminum Round Conductor 2. Roof conductor holder for parapet- Polyamide Conductor holder 3. Polyamide roof cable holder for flat roof 4. Cross universal connector: For T and cross connection 5. Expansion piece with connector 6. Connector: For T cross and parallel connectors 7. Vertical air terminal with accessories 8. Stand for Fang Fix system 16 kg with base and clamp 9. Connector to connect vertical Air terminal with horizontal conductor 10. 1 mtr vertical air terminal with mounting accessories	JOB	1	

11. Diagonal clamp. Installed with 2 hexagonal bolts 12. Cross connector for earth fixing point. Installed with 2 hexagonal bolts 13. Earth fixing point 14. Connector, Rd 8-10 mm with pressure 15. Lightning counter 16. Cross connector for Flat 17. Earthing pit & wiring Also, Any other Item Not included above but required to complete the Job. Final certification from OEM is required after complete installation. (with 24 months warranty)			
---	--	--	--

वर नमूद सुचित दर्शविलेल्या बाबींचे पुरवठा करणारे पुरवठादार/दुकानदार/उत्पादक/विक्रेते यांनी नमूद केलेल्या बाबींकरिता असलेले दर स्वतःच्या लेटरहेडवर महापालिकेच्या कार्यालयात अथवा ई-मेल द्वारे pmcbandhkamdept01@gmail.com /panvelcorporation@gmail.com यावर दिनांक 02 / 02/2026 पर्यंत पाठवावे ही विनंती, सदर दर हे अंदाजपत्रक तयार करणेसाठी गृहित धरणेत येणार आहेत.


शहर अभियंता
पनवेल महानगरपालिका

जा.क्र पमपा/बांधकाम/ 2222 /प्र.क्र.22/ 24/2026,
दि. 09/02/2026

प्रत माहितीस्तव — १. माहिती फलक करिता